



**V J T I**  
**Veermata Jijabai Technological Institute**  
(Central Technological Institute, Maharashtra State, INDIA)  
H. R. Mahajani Marg, Matunga, Mumbai 400019  
Tel.No. +91 22 24198101-02 Fax: +91 22 24102874  
[www.vjti.ac.in](http://www.vjti.ac.in)

Ref No.STR/Hostel/2704/2024

Date:- 07/08/2024

**8 AUG 2024**

**QUOTATION NOTICE**

M/s. ....

.....

.....

**Subject:- Repair and Painting works in Rooms and passages of first floor in C-block boy's hostel.**

**Enquiry Issue Date:- 07/08/2024**

**Last date of submission:- 16/08/2024 at 3.00 P.M.**

**Estimated Cost: Rs.8.20 Lakhs (Excluding GST)**

Dear Sir,

The Institute intends to undertake the Repair and Painting works in Rooms and passages of the first floor in C-Block Boy's Hostel for which sealed quotation are invited. You are requested to quote the rates/price/cost in Annexure – I.

**TERMS & CONDITIONS**

**1. Quotation submission**

- Sealed quotation, addressed to Director, VJTI; shall be posted or submitted at First Floor, Inward Section, VJTI, H. R. Mahajani Marg, Matunga, Mumbai 400019, in person so as to reach this Office on or before the due date and time.
- The sealed envelope shall be superscripted with Reference No. mentioned overleaf.
- Quotation must be printed on the **letterhead** of the firm/vendor/company/organization otherwise quotation shall be rejected outright.
- **Please mention your GST, PAN and any other relevant identification /registration numbers.**
- If the due date turns out to be a holiday for unforeseen reason, quotation should be accepted on the next working day.
- The quotation should be valid for a period of 60 days.
- The rate/price/cost quoted should be inclusive of all items, labour charges, transportation cost etc.

**2. Payment:-**

- **Payment after the satisfactory completion of work will be made by bank transfer only.**
- **As per Institute policy, no advance payment will be made.**

**3. Acceptance of quotation**

- Institute reserves the right of rejection of any or all the quotations without assigning any reasons.
- Canvassing in any form would lead to rejection of quotations.
- Quotations received after the due date will not be considered.
- Quotations without Signature and Stamp / Seal are likely to be rejected.
- Terms other than this may be specified separately.



**V J T I**

**Veermata Jijabai Technological Institute**

(Central Technological Institute, Maharashtra State, INDIA)

H. R. Mahajani Marg, Matunga, Mumbai 400019

Tel.No. +91 22 24198101-02 Fax: +91 22 24102874

[www.vjti.ac.in](http://www.vjti.ac.in)

□

#### 4. Additional Terms & Conditions:-

- i. The contractor should have experience in completion of similar type of work costing minimum 80% of estimated cost of the work during the last three years.
- ii. Site visit by the Bidder to understand the scope of work is compulsory for submission of quotation.
- iii. The experienced/qualified Supervisor (Diploma / Degree Civil Engineer) should be present at the worksite when work is in progress.
- iv. All the debris generated from the works is to be removed by the Contractor. It should be disposed of away from the Institute premises following Municipality rules.
- v. The work may be carried out on all days from 8.00 AM to 6.00 PM. For working in late hour's Dean (I & M) permission shall be obtained.
- vi. Successful bidder shall submit bar chart for the execution of work.
- vii. Duration: 30 days. Works should be completed within 30 calendar days from the date of work order.
- viii. An incentives of Rs.5,000/- per day will be given if work is completed early. A penalty of Rs.10,000/- per day will be levied if work is delayed.

**Dean (I & M)**





V J T I

**Veermata Jijabai Technological Institute**

(Central Technological Institute, Maharashtra State, INDIA)

H. R. Mahajani Marg, Matunga, Mumbai 400019

Tel.No. +91 22 24198101-02 Fax: +91 22 24102874

[www.vjti.ac.in](http://www.vjti.ac.in)

**Annexure – I ( Proforma for submission of price quote)  
Details of Painting and Repairing work in Boys Hostel (C-Block)**

Sr. No.	Description	Qty/Unit	Amount
1.	<p>1.Removing the existing cement plaster of any thickness without causing dust nuisance and stacking the debris upto a distance of 50 metres or stacking the same as and where directed including cleaning the site etc. complete (Area: around 200 sqm)</p> <p>2.Removing loose rust from the reinforcement bars by wire brushing, light hammering etc. and applying sulphate and chloride free inorganic single component rust remover Rusticide as approved (Area: around 50 sqm)</p> <p>3.Providing internal cement plaster 20mm thick in single coats in cement mortar 1:5 without neeru finish, to concrete, brick surface, in all positions including scaffolding and curing etc. complete (Area : around 200sqm)</p> <p>4. Scrapping the old plastered internal surface with sand paper and coating the entire surface with mixture of whitening of glue and linseed oil including scaffolding etc. complete as directed (Area: around 1500 sqm)</p> <p>5.Providing and applying Two coats of wall care putty on plastered surface and ceiling and walls to prepare surface even and smooth of approved make, etc complete (Area : around 1500 sqm)</p> <p>6. Providing and applying priming coat on concrete/ masonry/Asbestos Cement plastered surfaces including scaffolding if necessary, preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter and sand papering as required etc. complete (Area : around 1500 sqm)</p> <p>7.Providing and applying plastic emulsion paint of approved quality, colour and shade to old and new surfaces in three coats including scaffolding, preparing the surface. (Excluding primer coat). Etc. complete (Area: around 1500 sqm)</p> <p>8.Providng and applying priming coat over new wood and wood based surfaces, including preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter, sand papering and knotting, scaffolding etc. complete (Area: around 60 sqm)</p> <p>9.Providing and fixing glass panels for all the windows.</p> <p>10.Providing and applying melamine polish of required finish to the wood work by spray machine including knotting and preparing the even surface by scraping, applying French polish, scaffolding if required etc. complete.</p> <p>Note: The work to be executed on prior approval of Superintending Engineer will be necessary (Area: around 200 sqm)</p> <p>11.Providing and applying two coats of synthetic enamel paint of approved colour to new/old structural steel work and wood work in buildings, including scaffolding if necessary, cleaning and preparing the surface (excluding primer coat) etc. complete (Area: around 60 sqm)</p>	Lump sum	(Lumpsum price to be quoted by contractor) (To be printed on letter-head of contractor & to be submitted in sealed envelope)
	<b>Total Basic Amount:-</b>		
	<b>CGST 9%:-</b>		
	<b>SGST 9%:-</b>		
	<b>Total Amount:-</b>		

Dean (I & M)