



V J T I
Veermata Jijabai Technological Institute
(Central Technological Institute, Maharashtra State, INDIA)
H. R. Mahajani Marg, Matunga, Mumbai 400019
Tel.No. +91 22 24198101-02 Fax: +91 22 24102874
www.vjti.ac.in

Ref No. STR /Maintenance/ /2024

Date:-22/08/2024

QUOTATION NOTICE

M/s.

.....

.....

Subject:- Installation of new Distribution panel, MCCBs and cables behind SBI Branch at ground floor Mechanical Engineering Department.

Enquiry Issue Date:- 23/08/2024

Last date of submission:- 02/09/2024 at 4.00 P.M.

Estimated Cost: Rs.6.40 Lakhs (Including GST)

Dear Sir,

The Institute intends to undertake the Installation of new Distribution panel, MCCBs and cables behind SBI Branch at ground floor Mechanical Engineering Department for which sealed quotation are invited. You are requested to quote the rates/price/cost in Annexure – I.

TERMS & CONDITIONS

1. Quotation submission

- Sealed quotation, addressed to Director, VJTI; shall be posted or submitted at First Floor, Inward Section, VJTI, H. R. Mahajani Marg, Matunga, Mumbai 400019, in person so as to reach this Office on or before the due date and time.
- The sealed envelope shall be superscripted with Reference No. mentioned overleaf.
- Quotation must be printed on the **letterhead** of the firm/vendor/company/organization otherwise quotation shall be rejected outright.
- **Please mention your GST, PAN and any other relevant identification /registration numbers.**
- If the due date turns out to be a holiday for unforeseen reason, quotation should be accepted on the next working day.
- The quotation should be valid for a period of 60 days.
- The rate/price/cost quoted should be inclusive of all items, labour charges, transportation cost etc.

2. Payment:-

- **Payment after the satisfactory completion of work will be made by bank transfer only.**
- **As per Institute policy, no advance payment will be made.**

3. Acceptance of quotation

- Institute reserves the right of rejection of any or all the quotations without assigning any reasons.
- Canvassing in any form would lead to rejection of quotations.
- Quotations received after the due date will not be considered.
- Quotations without Signature and Stamp / Seal are likely to be rejected.
- Terms other than this may be specified separately.



V J T I

Veermata Jijabai Technological Institute

(Central Technological Institute, Maharashtra State, INDIA)

H. R. Mahajani Marg, Matunga, Mumbai 400019

Tel.No. +91 22 24198101-02 Fax: +91 22 24102874

www.vjti.ac.in

□

4. Additional Terms & Conditions:-

- i. The contractor should have experience in completion of similar type of work costing minimum 80% of estimated cost of the work during the last three years.
- ii. Site visit by the Bidder to understand the scope of work is compulsory for submission of quotation.
- iii. The experienced/qualified Supervisor (Diploma / Degree Civil Engineer) should be present at the worksite when work is in progress.
- iv. All the debris generated from the works is to be removed by the Contractor. It should be disposed of away from the Institute premises following Municipality rules.
- v. The work may be carried out on all days from 8.00 AM to 6.00 PM. For working in late hour's Dean (I & M) permission shall be obtained.
- vi. Successful bidder shall submit bar chart for the execution of work.
- vii. Duration: 30 days. Works should be completed within 30 calendar days from the date of work order.
- viii. An incentives of Rs.5,000/- per day will be given if work is completed early. A penalty of Rs.10,000/- per day will be levied if work is delayed.


Dean (I & M)



V J T I

Veermata Jijabai Technological Institute

(Central Technological Institute, Maharashtra State, INDIA)

H. R. Mahajani Marg, Matunga, Mumbai 400019

Tel.No. +91 22 24198101-02 Fax: +91 22 24102874

www.vjti.ac.in

**Annexure – I (Proforma for submission of price quote)
Details of Installation of New control panel and cabling, MCCB's at Meter Cabin Behind SBI)**

Sr. No.	Description	Qty	Unit	Rate	Amount
1.	Supply and Installation of Distribution panel 1) 400 Amps 4 pole MCCB -50K as Incomer-1set 2) All In One Metering section – 1set 3) Phase Indication Lamps-3 set 4) 200 Amps 4 pole MCCB-25KA as out going -2 nos. 5) 125 Amps 4 pole MCCB-25KA as out going -3 Nos. 6) 63 Amps 4 pole MCCB-25KA as out going – 1 No. 7) Aluminium Busbars – 1 set	1.00	Job		
2.	Supply and installation of cables to extend existing cable with suitable size and proper cable jointing. (Sizes will be 75sqmm, 50sqmm, 185sqmm Aluminium cable)	1.00	Job		
3.	Supply and Installation of copper flexible leads in Distribution panel from Main BEST supply.	1.00	Job		
4.	Charges for removing existing cable, switches etc.	1.00	Job		
5.	Dismnatling existing tilted wall 3.00m height 0.30m depth and 0.6 wide -1 nos, shifting debris, replastering, painting (area about 50 sq.m) etc complete.	1.00	Job		
Total Basic Amount:-					
CGST 9%:-					
SGST 9%:-					
Total Amount:-					

Dean (I & M)
Apr 8/24