



**V J T I**  
**Veermata Jijabai Technological Institute**  
(Central Technological Institute, Maharashtra State, INDIA)  
H. R. Mahajani Marg, Matunga, Mumbai 400019  
Tel.No. +91 22 24198101-02 Fax: +91 22 24102874  
[www.vjti.ac.in](http://www.vjti.ac.in)

Ref No. STR/I & M/ /2024

Date:- 28/10/2024

**QUOTATION NOTICE**

M/s. ....  
.....  
.....

**Subject:- Development of Central Testing Facility Laboratory of Mechanical Engineering Department.**

Enquiry Issue Date:- 28/10/2024

Last date of submission:- 06/11/2024 at 3.00 P.M.

Estimated Cost: Rs.9,52,940/-

Dear Sir,

The Institute intends to undertake the Development of Central Testing Facility Laboratory of Mechanical Engineering Department for which sealed quotation are invited. You are requested to quote the rates/price/cost in Annexure – I.

**TERMS & CONDITIONS**

**1. Quotation submission**

- Sealed quotation, addressed to Director, VJTI; shall be posted or submitted at First Floor, Inward Section, VJTI, H. R. Mahajani Marg, Matunga, Mumbai 400019, in person so as to reach this Office on or before the due date and time.
- The sealed envelope shall be superscripted with Reference No. mentioned overleaf.
- Quotation must be printed on the **letterhead** of the firm/vendor/company/organization otherwise quotation shall be rejected outright.
- **Please mention your GST, PAN and any other relevant identification /registration numbers.**
- If the due date turns out to be a holiday for unforeseen reason, quotation should be accepted on the next working day.
- The quotation should be valid for a period of 60 days.
- The rate/price/cost quoted should be inclusive of all items, labour charges, transportation cost etc.

**2. Payment:-**

- **Payment after the satisfactory completion of work will be made by bank transfer only.**
- **As per Institute policy, no advance payment will be made.**

**3. Acceptance of quotation**

- Institute reserves the right of rejection of any or all the quotations without assigning any reasons.
- Canvassing in any form would lead to rejection of quotations.
- Quotations received after the due date will not be considered.
- Quotations without Signature and Stamp / Seal are likely to be rejected.
- Terms other than this may be specified separately.



**V J T I**  
**Veermata Jijabai Technological Institute**  
(Central Technological Institute, Maharashtra State, INDIA)  
H. R. Mahajani Marg, Matunga, Mumbai 400019  
Tel.No. +91 22 24198101-02 Fax: +91 22 24102874  
[www.vjti.ac.in](http://www.vjti.ac.in)

□

#### 4. Additional Terms & Conditions:-

1. The contractor should have experience in completion of similar type of work costing minimum 80% of estimated cost of the work during the last three years.
2. Site visit by the Bidder to understand the scope of work is compulsory for submission of quotation.
3. The experienced/qualified Supervisor (Diploma / Degree Civil Engineer) should be present at the worksite when work is in progress.
4. All the debris generated from the works is to be removed by the Contractor. It should be disposed of away from the Institute premises following Municipality rules.
5. The work may be carried out on all days from 8.00 AM to 6.00 PM. For working in late hour's Dean (I & M) permission shall be obtained.
6. Successful bidder shall submit bar chart for the execution of work.
7. Duration: 60 days. Works should be completed within 30 calendar days from the date of work order.
8. An incentives of Rs.5,000/- per day will be given if work is completed early. A penalty of Rs.10,000/- per day will be levied if work is delayed.
9. Variation of +/- 25% in contract cost (Excess Qty/ Extra items) permitted with approval of Dean (I & M), subject to maximum contract cost of Rs.10 Lakhs.
10. Variation in contract cost (Excess Qty / Extra items) beyond 25% will be approved by Director.

Dean (I & M)



**V J T I**

**Veermata Jijabai Technological Institute**

(Central Technological Institute, Maharashtra State, INDIA)

H. R. Mahajani Marg, Matunga, Mumbai 400019

Tel.No. +91 22 24198101-02 Fax: +91 22 24102874

[www.vjti.ac.in](http://www.vjti.ac.in)

**Annexure – I ( Proforma for submission of price quote)  
Details of Central Testing Facility Laboratory of Mechanical Engineering Department.**

Sr. No.	Description	Qty	Unit	Rate	Amount
1.	Scrapping the old plastered internal surface with Machine and coating the entire surface with mixture of whitening or glue and linseed oil including scaffolding etc. complete as directed	322.00	SqM		
2.	Providing and applying Two coats of wall care Putty on plastered surface and Ceiling and Walls to prepare surface even and smooth of approved make, etc complete	105.00	SqM		
3.	Providing and applying priming coat on concrete/ masonry/ Asbestos Cement plastered surfaces including scaffolding if necessary, preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter and sand papering as required etc. complete	322.00	SqM		
4.	Providing and applying interior wall finish luster of approved make on internal wall surface as detailed below Scrapping the surface with emery paper and wipe clean wall primer with brush with mineral turpentine with brush 8 to 10% and oil 15 to 20% with roller and allowing to dry for a period 6 to 8 hours. wall putty with appropriate proportion of water allowing to dry for period 4 to 6 hours. Scrapping with Emery paper 180 and wipe clean. Applying wall primer with brush with mineral turpentine 8 to 10% and oil 15 to 20% with roller Scrapping Emery paper 320 and wipe clean, interior wall finish luster 1st coat with brush/rubber/spray with mineral turpentine 7 to 9% and Oil with roller 19 to 21% After 8 hours of activity Applying 2nd coat or wall finish Lustre with mineral turpentine 7 to 9 % with brush and Oil with roller 19 to 21% after allowing dry for the period of 6 to 8 hours activity. (With prior approval of S.E.)	322.00	SqM		
5.	Providing and laying telephone black / Amba White / Cadburybrown / Ruby red / Ocean Brown granite stone of 18 to 20 mm thick for door frame/ dado/ window boxing etc. On C.M. 1:6 including filling joints with polymer base filler nosing/moulding the sharp edges wherever necessary, curing, etc. complete.	7.00	SqM		
6.	Providing and fixing in position (as per 1868 / 1982) Aluminium sliding window of three tracks with rectangular pipe 95 x 38.10 x 0.90 mm at weight 0.637 Kilogram/One Running Metre. with window frame bottom track section 92 x 31.75 x 1.30 mm at weight 1.070 Kilogram/One Running Metre.. Top and side track section 92 x 31.75 x 1.30 mm at weight 0.933 Kilogram/Running metre. The shutter should be of bearing bottom 40 x 18 x 1.25 mm at weight 0.417 Kilogram/One Running Metre. Inter locking section 40 x 18 x 1.10 mm at weight 0.469 Kilogram/Running metre. and handle and top section 40 x 18 x 1.25 mm at weight 0.417 Kilogram/Running metre. As per detailed drawings and as directed by Engineer incharge with all necessary Aluminium sections fixtures and fastenings such as roller bearing in nylon casting and self locking catch fitted in vertical section of shutter including 5 mm thick plain glass and aluminium mosquito net shutter with stainless steel jail with all required screws and nuts etc, complete. With colour Anodising without box	13.00	SqM		



Sr. No.	Description	Qty	Unit	Rate	Amount
7.	Providing and laying Polished Kota stone flooring With Hand-Cut Polished Kota Stones 25mm to 30mm thick and required width in plain/diamond pattern on bed of 1:6 Cement mortar including cement float, filling joints with neat cement slurry, curing, cleaning and Mirror Polishing etc. complete Note- Water absorption for kota stone should not exceed 0.05%.	125.00	SqM		
8.	Providing Mirror polishing to Kota Stone including using all necessary stones and equipments cleaning, washing etc. complete. For Flooring	105.00	SqM		
9.	Providing and fixing Modular false ceiling of 600 x 600 mm center to center and 13 mm thick square PVC Board to be fixed on frame work of alluminium sections for suspended false ceiling consisting of alluminium T 2"x1 1/2" (50 mm x 40 mm) weighing 0.39 Kilogram/m at 60 cms center center and fixed with 1/2" x 1/2" (15 x 15 mm) flanges weighing 0.19 Kilogram/m suspended on 6 mm dia mild steel rod weighing 0.22 Kilogram/m, fixed on wall and beams including rounding of the edges with alluminium T of 2" x 1 1/2" (50 mm x 40 mm) weighing 0.39 Kilogram/m etc. (all alluminium sections shall be anodized) including all labour, material, lifts etc. complete.	103.00	SqM		
10.	Structural Strengthening of slab, beam and coloum in Dept. Library.	1.00	LS.		
11.	Providing and fixing solid core flush door shutter in single leaf 32 mm thick decorative type of exterior grade as per detailed drawings approved face veneers 3 mm thick on both faces or as directed, all necessary beads, mouldings and lipping, wrought iron hold fasts, chromium plated fixtures and fastenings, with brass mortise lock, chromium plated handles on both sides, and finishing with French Polish etc. complete. Base price of solid core flush doors Rs.1050/- per sq.m	7.00	SqM		
12.	Providing and fixing green marble of 18 to 20 mm thick for door frame/ dado/window boxing etc. On C.M. 1:6 including filling joints with polymer base filler nosing /moulding the sharp edges wherever necessary, curing, etc. complete. Base price of green marble Rs.1303/- per sq.m	3.00	SqM		
13.	Providing Mirror polishing to Kota Stone including using all necessary stones and equipments cleaning, washing etc. complete. For Flooring	125.00	SqM		
<b>Total Basic Amount:-</b>					
<b>CGST 9%:-</b>					
<b>SGST 9%:-</b>					
<b>Total Amount:-</b>					

  
 Dean (I & M)