



V J T I

Veermata Jijabai Technological Institute

(Central Technological Institute, Maharashtra State, INDIA)

H. R. Mahajani Marg, Matunga, Mumbai 400019

Tel.No. +91 22 24198101-02 Fax: +91 22 24102874

www.vjti.ac.in

Ref No. STR/I & M/416 /2024

Date:- 04/11/2024

4 NOV 2024

QUOTATION NOTICE

M/s.

.....

.....

- Subject:-**
- A. Supply and Installation of New Distribution Board for SRA at Mechanical Department**
 - B. Supply & Installation of Distribution Board at Production Department**
 - C. Supply and laying of new cable and starter for existing pump from Electrical Department Main panel to pump room near Canteen.**

Enquiry Issue Date:- 04/11/2024

Last date of submission:- 11/11/2024 at 3.00 P.M.

Estimated Cost: Rs.3,80,905/- (Including GST)

Dear Sir,

The Institute intends to undertake the A. Supply and Installation of New Distribution Board for SRA at Mechanical Department B. Supply & Installation of Distribution Board at Production Department. C. Supply and laying of new cable and starter for existing pump from Electrical Department Main panel to pump room near Canteen for which sealed quotation are invited. You are requested to quote the rates/price/cost in Annexure – I.

TERMS & CONDITIONS

1. Quotation submission

- Sealed quotation, addressed to Director, VJTI; shall be posted or submitted at First Floor, Inward Section, VJTI, H. R. Mahajani Marg, Matunga, Mumbai 400019, in person so as to reach this Office on or before the due date and time.
- The sealed envelope shall be superscripted with Reference No. mentioned overleaf.
- Quotation must be printed on the **letterhead** of the firm/vendor/company/organization otherwise quotation shall be rejected outright.
- **Please mention your GST, PAN and any other relevant identification /registration numbers.**
- If the due date turns out to be a holiday for unforeseen reason, quotation should be accepted on the next working day.
- The quotation should be valid for a period of 60 days.
- The rate/price/cost quoted should be inclusive of all items, labour charges, transportation cost etc.

2. Payment:-

- **Payment after the satisfactory completion of work will be made by bank transfer only.**
- **As per Institute policy, no advance payment will be made.**

3. Acceptance of quotation

- Institute reserves the right of rejection of any or all the quotations without assigning any reasons.
- Canvassing in any form would lead to rejection of quotations.
- Quotations received after the due date will not be considered.
- Quotations without Signature and Stamp / Seal are likely to be rejected.
- • Terms other than this may be specified separately.

4. Additional Terms & Conditions:-

11. The contractor should have experience in completion of similar type of work costing minimum 80% of estimated cost of the work during the last three years.
12. Site visit by the Bidder to understand the scope of work is compulsory for submission of quotation.
13. The experienced/qualified Supervisor (Diploma / Degree Civil Engineer) should be present at the worksite when work is in progress.
14. All the debris generated from the works is to be removed by the Contractor. It should be disposed of away from the Institute premises following Municipality rules.
15. The work may be carried out on all days from 8.00 AM to 6.00 PM. For working in late hour's Dean (I & M) permission shall be obtained.
16. Successful bidder shall submit bar chart for the execution of work.
17. Duration: 60 days. Works should be completed within 30 calendar days from the date of work order.
18. An incentives of Rs.5,000/- per day will be given if work is completed early. A penalty of Rs.10,000/- per day will be levied if work is delayed.
19. Variation of +/- 25% in contract cost (Excess Qty/ Extra items) permitted with approval of Dean (I & M), subject to maximum contract cost of Rs.10 Lakhs.
20. Variation in contract cost (Excess Qty / Extra items) beyond 25% will be approved by Director.


Dean (I & M)
25/10/24



V J T I
Veermata Jijabai Technological Institute
 (Central Technological Institute, Maharashtra State, INDIA)
 H. R. Mahajani Marg, Matunga, Mumbai 400019
 Tel.No. +91 22 24198101-02 Fax: +91 22 24102874
www.vjti.ac.in

Annexure – I (Proforma for submission of price quote)

Details Specification are as follows:-

- A. Supply and Installation of New Distribution Board for SRA at Mechanical Department**
B. Supply & Installation of Distribution Board at Production Department.
C. Supply and laying of new cable and starter for existing pump from Electrical Department
Main panel to pump room near Canteen.

Sr. No.	Description	Qty	Unit	Rate	Amount
A.	Supply and Installation of New Distribution Board for SRA at Mechanical Department.				
1.	Providing & erecting floor / wall mounting, MCCB panel board with door suitable for four pole incoming 400 A, four pole outgoing upto 200 A MCCB's on iron frame, as per specification no SW-SWR/MCCBPB. (Excluding MCCB'S)				
3.	Providing & erecting 3 Pole MCCB of 315/400 A, 415V capacity with short circuit rating 36 kA (Ics=100% of Icu), adjustable thermal (overload) setting and fixed magnetic setting with provided leads, provision for installation of shunt/UV/ trip alarm contact and MCCB should have phase barriers both sides, in provided enclosure.				
4.	Providing & erecting 3 Pole MCCB of 250A,415V capacity with short circuit rating 36 kA (Ics=100% of Icu) adjustable thermal (overload) setting and fixed magnetic setting with provided leads, provision for installation of shunt/ UV/ trip alarm contact and MCCB should have phase barriers both sides, in provided enclosure.				
5.	Supplying, erecting & marking FPMCB 40A to 63A in provided distribution board.				
6.	Supplying & erecting CRCA sheet metal one-way enclosures suitable for DP MCB /TP MCB /FP MCB erected on angle iron/GI frame complete.				
7.	Supply and Installation of cable termination of 3C x 120 Sqmm. armoured cable.				
8.	Labour charges for removing old cable, old main switches, DBs etc.				
B.	Supply & Installation of Distribution Board at Production Department.				
1.	Supplying, erecting XLPE armoured cable 4 core 16 sq. mm. copper conductor continuous 5.48 sq.mm. (12 SWG) Copper earth wire complete erected on wall/ trusses/ pole or laid in provided trench/ pipe as per specification.				
2.	Supply and Installation Legrand make 4-way DB.				
3.	Supply and Installation of 125 AMP. TP. MCCB main incomer.				
4.	Supply and erection 63 AMP SP MCB For outgoing.				
5.	Removing old cables, old main switch and other related work.				

Sr. No.	Description	Qty	Unit	Rate	Amount
C.	Supply and laying of new cable and Starter for existing pump from Electrical Department Main Panel to Pump room near Canteen.				
1.	Supplying, erecting XLPE armoured cable 4 core 6 sq. mm. copper conductor continuous 5.48 sq.mm. (12 SWG) Copper earth wire complete erected on wall/ trusses/ pole or laid in provided trench/ pipe as per specification.				
2.	Supplying, erecting XLPE armoured cable 4core 4 sq. mm. copper conductor continuous 5.48 sq.mm. (12 SWG) Copper earth wire complete erected on wall/ trusses/ pole or laid in provided trench/ pipe as per specification.				
3.	Supplying & erecting CRCA sheet metal one-way enclosures suitable for DP MCB /TP MCB /FP MCB erected on angle iron/GI frame complete.				
4.	Supply and Installation of DOL Starter.				
5.	Supplying, erecting & marking FP MCB 40A to 63A in provided distribution board as per specification.				
	Total Amount:-				
	CGST 9% :-				
	SGST 9% :-				
	Net Amount:-				



Dean (I & M)

25/10/24