



V J T I
Veermata Jijabai Technological Institute
(Central Technological Institute, Maharashtra State, INDIA)
H. R. Mahajani Marg, Matunga, Mumbai 400019
Tel.No. +91 22 24198101-02 Fax: +91 22 24102874
www.vjti.ac.in

Ref No. STR/I & M/ ⁴⁷¹³ /2024

Date:- 02/12/2024
5 DEC 2024

QUOTATION NOTICE

M/s.
.....
.....

Subject:- Civil Repair and Painting Jobs in Electrical Department (Staircase and all internal Labs of 1st Floor.)

Enquiry Issue Date:- 02/12/2024

Last date of submission:- 12/12/2024 at 3.00 P.M.

Estimated Cost: Rs.8,13,800/- (Including GST)

Dear Sir,

The Institute intends to undertake the Civil Repair and Painting Jobs in Electrical Department (Staircase and all internal Labs of 1st Floor.) for which sealed quotation are invited. You are requested to quote the rates/price/cost in Annexure – I.

TERMS & CONDITIONS

1. Quotation submission

- Sealed quotation, addressed to Director, VJTI; shall be posted or submitted at First Floor, Inward Section, VJTI, H. R. Mahajani Marg, Matunga, Mumbai 400019, in person so as to reach this Office on or before the due date and time.
- The sealed envelope shall be superscripted with Reference No. mentioned overleaf.
- Quotation must be printed on the **letterhead** of the firm/vendor/company/organization otherwise quotation shall be rejected outright.
- **Please mention your GST, PAN and any other relevant identification /registration numbers.**
- If the due date turns out to be a holiday for unforeseen reason, quotation should be accepted on the next working day.
- The quotation should be valid for a period of 60 days.
- The rate/price/cost quoted should be inclusive of all items, labour charges, transportation cost etc.

2. Payment:-

- **Payment after the satisfactory completion of work will be made by bank transfer only.**
- **As per Institute policy, no advance payment will be made.**

3. Acceptance of quotation

- Institute reserves the right of rejection of any or all the quotations without assigning any reasons.
- Canvassing in any form would lead to rejection of quotations.
- Quotations received after the due date will not be considered.
- Quotations without Signature and Stamp / Seal are likely to be rejected.
- Terms other than this may be specified separately.

□

4. Additional Terms & Conditions:-

1. The contractor should have experience in completion of similar type of work costing minimum 80% of estimated cost of the work during the last three years.
2. Site visit by the Bidder to understand the scope of work is compulsory for submission of quotation.
3. The experienced/qualified Supervisor (Diploma / Degree Civil Engineer) should be present at the worksite when work is in progress.
4. All the debris generated from the works is to be removed by the Contractor. It should be disposed of away from the Institute premises following Municipality rules.
5. The work may be carried out on all days from 8.00 AM to 6.00 PM. For working in late hour's Dean (I & M) permission shall be obtained.
6. Successful bidder shall submit bar chart for the execution of work.
7. Duration: 60 days. Works should be completed within 30 calendar days from the date of work order.
8. An incentives of Rs.5,000/- per day will be given if work is completed early. A penalty of Rs.10,000/- per day will be levied if work is delayed.
9. Variation of +/- 25% in contract cost (Excess Qty/ Extra items) permitted with approval of Dean (I & M), subject to maximum contract cost of Rs.10 Lakhs.
10. Variation in contract cost (Excess Qty / Extra items) beyond 25% will be approved by Director.



Dean I & M


27/12/2024



V J T I

Veermata Jijabai Technological Institute

(Central Technological Institute, Maharashtra State, INDIA)

H. R. Mahajani Marg, Matunga, Mumbai 400019

Tel.No. +91 22 24198101-02 Fax: +91 22 24102874

www.vjti.ac.in

Annexure – I (Proforma for submission of price quote)

**Details Specification are as follows:- Civil Repair and Painting Jobs in Electrical Department
(Staircase and all internal Labs of 1st Floor.)**

Sr. No.	Description	Qty	Unit	Rate	Amount
1	Providing& Applying chemical for cleaning the exposed steel structure,TMTbars,etc. of structure by grinding the surface by grinder machine,wirebrush, removing existing corrosion from the metal also removing loose particles, of the area by water jet, (usingother mechanical / manual means) and apply on prepared surface of as corrosion preventive coat on prepared TMT bars,steel structure,metal surface etc. to protect it from corrosion etc. as per manufacturer's specification (usingother manual / mechanical means) after that Providingand applying high abrasive resistant, self curing, UV resistant,impermeable,high strength,non shrink, Poly Ironite Ceramic Cementitious (PICC) repair mortar resurfacing onconcrete surface of thickness up to 10mm including breaking honey comb area, (using manual/mechanical means) , clean the concrete surface with special chemical clonon with pressure water jet for removing of algaefungi,apply bondcoat Kelox water misible epoxy before PICC application with all lead sandlifts,Material,Machinery labour,scaffolding, etc. complete as per specification and as directed by engineer-in-charge.	5.00	Sqm		
2	Providing and applying 50 mm thick self-curing Ceramic Polymer Micro concrete of approved make having Compressive strength above M30, no shrink, impermeable, filling mortar to load carrying R.C.C member in two layers on cleaned concrete surface, including honeycomb area (using manual/mechanical means). Mixing mortar of Nicosil C80 and fresh 53 grade cement with required water cement ratio for desired consistency and applying and finishing by manual trowelling, curing after curing initial setting time etc, as per manufacturers specification etc. complete as per specification and as directed by engineer-in-charge. Work shall be executed by certified applicator only and work shall be guaranteed for 5 years and guarantee shall be provided on Rs.500/- stamp paper. (Bond coat mentioned below is to be done before coating)	2.00	Sqm		
3	Removing the existing cement plaster of any thickness without causing dust nuisance and stacking the debris upto a distance of 50 metres or spreading in the compound and cleaning the site etc. complete	50.00	Sqm		

Sr. No.	Description	Qty	Unit	Rate	Amount
4	Providing Internal/External 20 mm thick Ready Mix plaster of 1:4 mix ratio confirming to IS:4031 (Part 4) 1988 and IS:383-1970 in a single coat containing special type of polymer additive about 0.4%, to all type of surfaces in all positions including scaffolding and curing etc. complete.	50.00	Sqm		
5	The scope of work involves scraping and removing all the paint layers till plaster from the internal surfaces using sandpaper and a grinding machine. All existing paint coatings will be removed down to the plaster surface. Scaffolding will be set up as needed to ensure safe access to all areas. The work will be completed as directed by the engineer in charge.	2400.00	Sqm		
6	Providing and applying priming coat on concrete/ masonry/ Asbestos Cement plastered surfaces including scaffolding if necessary, preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter and sand papering as required etc. complete.	2400.00	Sqm		
7	Providing and applying Two coats of wall care Putty on plastered surface and Ceiling and Walls to prepare surface even and smooth of approved make, etc complete.	2400.00	Sqm		
8	Providing and applying plastic emulsion paint of approved quantity, colour and shade to old and new surfaces in two coats including scaffolding, preparing the surfaces. (excluding the primer coat.) etc. complete.	2400.00	Sqm		
9	Providing and applying priming coat over new wood and wood based surfaces, including preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter, sand papering and knotting, scaffolding etc. complete.	200.00	Sqm		
10	Providing and applying two coats of synthetic enamel paint of approved colour to new/old structural steel work and wood work in buildings, including scaffolding if necessary, cleaning and preparing the surface (excluding primer coat) etc. complete.	200.00	Sqm		
11	For removal of any kind of debris as per SSR-Statement C1 for lead 50 KM	4.00	Cum		
	Total Amount:-				
	CGST 9% :-				
	SGST 9% :-				
	Net Amount:-				



Dean (I & M)