



**V J T I**

**Veermata Jijabai Technological Institute**

(Central Technological Institute, Maharashtra State, INDIA)

H. R. Mahajani Marg, Matunga, Mumbai 400019

Tel.No. +91 22 24198101-02 Fax: +91 22 24102874

[www.vjti.ac.in](http://www.vjti.ac.in)

□

Ref No. STR/Maintenance/ 558 /2025

Date:- 13/05/2025

**13 MAY 2025**

**QUOTATION NOTICE**

M/s. ....

**Subject:- Repairs and Replacement of Mangalore roof tiles at Structural Engineering Department for monsoon protection.**

**Enquiry Issue Date:- 13/05/2025**

**Last date of Submission:- Immediate**

**Estimated Cost: Rs. 9,84,336/- (Including GST)**

Dear Sir,

The Institute intends to undertake Construction of a Repairs and Replacement of Mangalore roof tiles at Structural Engineering Department for monsoon protection in the Institute for which sealed quotation are invited. You are requested to quote the rates/price/cost in Annexure – I.

**TERMS & CONDITIONS**

**1. Quotation submission**

- Sealed quotation, addressed to Director, VJTI; shall be posted or submitted at First Floor, Inward Section, VJTI, H. R. Mahajani Marg, Matunga, Mumbai 400019, in person so as to reach this Office on or before the due date and time.
- The sealed envelope shall be superscripted with Reference No. mentioned overleaf.
- Quotation must be printed on the **letterhead** of the firm/vendor/company/organization otherwise quotation shall be rejected outright.
- **Please mention your GST, PAN and any other relevant identification /registration numbers.**
- If the due date turns out to be a holiday for unforeseen reason, quotation should be accepted on the next working day.
- The quotation should be valid for a period of 60 days.
- The rate/price/cost quoted should be inclusive of all items, labour charges, transportation cost etc.

**2. Payment:-**

- **Payment after the satisfactory completion of work will be made by bank transfer only.**
- **As per Institute policy, no advance payment will be made.**

**3. Acceptance of quotation**

- Institute reserves the right of rejection of any or all the quotations without assigning any reasons.
- Canvassing in any form would lead to rejection of quotations.
- Quotations received after the due date will not be considered.
- Quotations without Signature and Stamp / Seal are likely to be rejected.
- Terms other than this may be specified separately.

### **Additional Terms & Conditions:-**

1. The contractor should have experience in completion of similar type of work costing minimum 80% of estimated cost of the work during the last three years.
2. Site visit by the Bidder to understand the scope of work is compulsory for submission of quotation.
3. The experienced/qualified Supervisor (Diploma / Degree Civil Engineer) should be present at the worksite when work is in progress.
4. All the debris generated from the works is to be removed by the Contractor. It should be disposed of away from the Institute premises following Municipality rules.
5. The work may be carried out on all days from 8.00 AM to 6.00 PM. For working in late hour's Dean (I & M) permission shall be obtained.
6. Successful bidder shall submit bar chart for the execution of work.
7. Duration: 30 days. Works should be completed within 30 calendar days from the date of work order.
8. An incentives of Rs.5,000/- per day will be given if work is completed early. A penalty of Rs.10,000/- per day will be levied if work is delayed.
9. The Pre-bid meeting will be held on dt:15/05/2025 at 3.00pm in structural department seminar hall to understand the scope of work.



Dean (I & M)  
Seal

□

**Annexure – I ( Proforma for submission of price quote)**

**Details Specification are as follows Repairs and Replacement of Mangalore roof tiles  
at Structural Engineering Department for monsoon protection.**

Sr. No.	Description	Qty	Unit	Rate	Total Amount
1.	Removing and resetting Mangalore tiles from roof including refixing loose battens etc. complete.	1500.00	sqm.		
2.	Providing fixing Mangalore tile roofing with class AA tiles in cement mortar 1:4 on sloping slab including necessary scaffolding, curing, finishing, etc. complete.	450.00	sqm.		
3.	Providing and fixing Mangalore tile ridge and hip tiles of class' AA' including scaffolding if necessary, pointing with coloured cement mortar and curing etc. complete.	75.00	rmt.		
4.	Providing fixing country teak wood battens 50mmx25mm for Mangalore tile roof work with all iron work scaffolding and oiling the battens etc. complete.	500.00	rmt.		
5.	Providing and fixing 22 B.W.G. plain FRP sheets on top of weather shed, including scaffolding, fixing by means of nut and bolts or as directed etc. complete.	20.00	sqm.		
	<b>Total Basic Amount</b>				
	<b>Add CGST 9%</b>				
	<b>Add SGST 9%</b>				
	<b>Net Amount</b>				

  
**Dean (I & M)**  
Seal